

15-185-00176-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 14 Twp. 23 Rge. (E)14 (W)

Location as "NE/CNW/SW" or footage from lines SE NW SW

Lease Owner Westgate-Greenland Oil Company

Lease Name Taylor Well No. 1

Office Address 1009 Central Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed January 23, 1953 19

Application for plugging filed (orally) January 23, 1953 19

Application for plugging approved January 23, 1953 19


Plugging commenced January 23, 1953 19

Plugging completed 7:30 P M January 23, 1953 19

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface		0	203	.10 3/4"	203	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 4038 to 200 feet
Set plug at 200 feet and ran 25 sacks cement to 150 feet
Filled with heavy mud from 150 feet to 20 feet
Set plug ~~and~~ at 20 feet and ran 10 sacks cement to cellar.

RECEIVED
STATE CC, P...
MISSION

1-28-53

CONS... DIVISION

Name of Plugging Contractor Westgate Drilling Corporation
Address 1009 Central Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler

1009 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 1953

Eather Russell
Notary Public.

My commission expires May 25, 1953.

PLUGGING
FILE SEC 14 T 23 R 143
BOOK PAGE 25 LINE 4

15-185-60176-0000

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: Westgate Drilling Corporation
 FARM: Taylor #1, SE NW SW 14-23S-14W,
 Stafford County, Kansas
 COMMENCED: January 10, 1953
 COMPLETED: January 23, 1953
 ELEVATION: 1931 DF

0	to	70	S. Sand and gravel
70	to	290	Shale and shells
290	to	370	Sand and red bed
370	to	835	Shale and red bed
835	to	865	Anhydrite
865	to	1765	Shale and shells
1765	to	2026	Lime and shale
2026	to	2300	Lime
2300	to	3555	Lime and shale
3555	to	3780	Lime
3780	to	3923	Lime and shale
3923	to	3948	Lime
3948	to	3979	Shale and lime
3979	to	4022	Shale
4022	to	4038	Arbuckle
		4038	T. D. (RB)

Set 203 feet of 10 3/4" surface pipe. Cemented with 250 sacks cement.

DST #1 3654-71, open 1 hour, 5 minute weak blow, recovered 62 feet mud, no BHP.
 #2 3697-3741, open 1 hour, weak blow thruout, rec. 65 feet mud, BHP 1290#.
 #3 4001-20, strong blow, open 1 hour, recovered 1700 feet sulphur water, BHP 1250#.

TOPS: Anhydrite	833	Lansing	3539	Viola	3884
Heebner	3392	Base KC	3784	Simpson	3954
Brown L.	3525	Chert, Cong	3871	Arbuckle	3999

Schlumberger Run.

DRY, PLUGGED AND ABANDONED

C E R T I F I C A T E

I, Don Allen, do hereby certify that the above and foregoing is a true and correct copy of log of the Taylor No. 1, SE NW SW Section 14-23S-14W, Stafford County, Kansas, as reflected by files of the Westgate Drilling Corporation.

Don Allen
 Don Allen

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 27th day of January, 1953.

Esther Unsell
 Esther Unsell, Notary Public

My commission expires May 25, 1953.

PLUGGING
 FILE SEC 14 T 23 R 14
 BOOK PAGE 75 LINE 4

RECORDED
 STATE OF KANSAS
 COUNTY OF SEDGWICK
 DIVISION