

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-093-00259-0000

LEASE NAME ROSS GAS UNIT

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2640 Ft. from ^N Section Line

2640 Ft. from E Section Line

LEASE OPERATOR Amoco Production Company

SEC. 34 TWP. 21 RGE. 35 (E) or (W)

ADDRESS P.O. Box 3092 Room 3 200, Houston, TX 77253 COUNTY KEARNY

PHONE# (281) 366-7816 OPERATORS LICENSE NO. 5952 Date Well Completed 1-27-47

Character of Well GAS Plugging Commenced 11-8-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 11-8-00

The plugging proposal was approved on 8-14-00 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation CHASE Depth to Top 2628' Bottom 2774' T.D. 2830'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	<u>SURFACE</u>			<u>8 5/8"</u>	<u>1002'</u>	<u>0'</u>
	<u>PRODUCTION</u>			<u>5 1/2"</u>	<u>2798'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
PUMP 40 SKS CEMENT & 250 # HULLS FILL FROM 2629-2730', SET
C.T.B.P @ 1030', PERF 4 SKS @ 1020', PUMP 190 SKS CEMENT
FILL 5 1/2 CASING & ANNULUS BETWEEN 5 1/2" & 8 5/8", TOTAL CEMENT USED
230 SKS CLASS "C" 65/35 6% GEL 12.3 # 1 GAL - 2.02 ea FT / SK YIELD

(If additional description is necessary, use BACK of this form.)

JOB WITNESSED BY KEVIN STRUBE W/KCL ON 11-8-00
Name of Plugging Contractor HALLIBURTON SERVICES License No. 5287

Address _____ RECEIVED KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company

STATE OF Texas COUNTY OF Harris, ss.


Lou Barry (Employee of Operator) (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature) Lou Barry

(Address) _____

SUBSCRIBED AND SWORN TO before me this 5th day of December, 2000



Nikita R. Macres
Notary Public



My Commission Expires _____