

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Finney County, Sec. 27 Twp. 21 Rge. 34 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner The Shallow Water Refining Company

Lease Name Nunn Well No. 2

Office Address Ward Parkway Bank Bldg., Country Club Plaza, Kansas City/

Character of Well (completed as Oil, Gas or Dry Hole) Oil 12, Missouri

Date well completed 10 - 16 1944

Application for plugging filed 5 - 14 1956

Application for plugging approved 5 - 15 1956

Plugging commenced 5 - 25 1956

Plugging completed 5 - 29 1956

Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production 4 - 10 1956

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Gordon Farr

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4754 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Oil	4640'	4725'	10 3/4"	261'	None
				5 1/2"	4616'	935'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole and found bottom at 4754'. Filled with sand to 4610'. Dumped 2 sacks cement. Cement filled hole to 4596. Ran 320 Gal. of sand to 4260'. Dumped 3 sacks cement. Found top of cement 4245'. Bailed fluid from 160' to 290'. Rock bridge at 270'. Dumped 30 sacks cement. Checked cement at 247'. Mudded to 30' from top. Rock bridge to 20'. Dumped 10 sacks cement. Filled to 6' from surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Finney, ss.

Ben I. Kelley (employee of owner) or _____ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben I. Kelley

801 East Walnut, Garden City, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of June, 19 56

My commission expires December 10, 1958

Notary Public. STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 27 T. 21 R. 34w
BOOK PAGE 61 LINE 13

JUN 25 1956 6-25-56
CONSERVATION DIVISION

W E L L L O G

NUNN NO. 2

C NE/4 NE/4 of Section 27-21S-34W
Finney County, Kansas

Commenced w/ rotary tools - 7/2/44

Completed w/ cable tools - 10/16/44

Set 10 3/4" surface casing at 261' w/ 200 sacks

Set 5 1/2" casing at 4616' w/ 175 sacks

<u>Formation</u>	<u>Top</u>	<u>Bottom</u>
Surface sand and gravel	0	350
Shale and shells	350	590
Sand	590	750
Shale and shells	750	1140
Redbed and shells	1140	1360
Redbed, gyp and shale	1360	1440
Redbed, shale and anhydrite	1440	1525
Redbed, shale and salt	1525	1860
Redbed, shale and shells	1860	1905
Redbed, and shale	1905	1970
Redbed, shale and shells	1970	2130
Lime and shale	2130	2135
Redbed, shale and lime	2135	2355
Lime and shale	2355	2980
Lime	2980	3285
Lime and shale	3285	3840
Lime	3840	4553
Lime and shale	4553	4607
Shaley sandstone and lime	4607	4630
Lime	4630	4643
Limey sandstone	4643	4660
Sandy lime	4660	4666
Dense lime	4666	4674
Lime	4674	4704
Lime	4704	4754 TD

I, Ben L. Kelley, hereby certify that the above log is true and correct to the best of my knowledge and belief.


Ben L. Kelley

Subscribed and sworn to before me this 14th day of May, 1956.

James M. Burnett
Notary Public
STATE OF KANSAS

My Commission Expires

December 10, 1958



MAY 15 1956
CONSERVATION DIVISION
Wichita, Kansas