

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Finney County, Sec. 34 Twp. 21S Rge. 34 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NW SW  
Lease Owner The Shallow Water Refining Company  
Lease Name Aeilts Well No. 4  
Office Address Ward Parkway Bank Bldg., Country Club Plaza, Kansas City  
Character of Well (completed as Oil, Gas or Dry Hole) Oil 12, Mo.  
Date well completed May 5, 1951  
Application for plugging filed July 31, 1956  
Application for plugging approved August 1, 1956  
Plugging commenced October 19, 1956  
Plugging completed October 29, 1956  
Reason for abandonment of well or producing formation Non-commercial

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production August 3, 1956  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation Marmaton Depth to top 4308' Bottom 4320' Total Depth of Well 4762' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	300'	None
				5 1/2"	4743'	1996'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Lane-Wells plug set at 4350'. Filled with sand from 4350' to 4300'. Dumped 5 sacks cement, filled up to 4260'. Shot pipe at 1996', pulled up to 1800'. Circulated 20 sacks chemical mud. Pulled out pipe. Set plug in surface pipe at 295'. Filled up with 20 sacks cement, then mud to 30' of top. Set rock bridge, then dumped 5 sacks cement, filling hole to base of cellar.

RECEIVED  
OCT 29 1956  
CONSERVATION DIVISION  
Wichita, Kansas  
11-2-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Finney, ss.  
Ben L. Kelley (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben L. Kelley  
801 East Walnut St., Garden City, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of October, 1956

My commission expires December 10, 1958

[Signature]  
Notary Public.

PLUGGING  
FILE SEC. 34 T. 21 R. 34W  
BOOK PAGE 86 LINE 4

AEILTS NO. 4

Rigging up Rotary Tools 4/7/51  
 Tearing down Rotary Tools 5/5/51

Run 15 Jts. 8 5/8" surface pipe.  
 Set at 300' and cemented with 150  
 sacks cement


Run 133 Jts. 5 1/2" casing. set at 4743'  
 and cemented with 300 sx cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface sand and clay	0	127
Sand, clay and shells	127	300
Shale and sand	300	1045
Shale and shells	1045	1515
Shale, shells, sand	1515	1766
Shells and shale	1766	2335
Lime and shale	2335	2513
Lime, shale, sandy	2513	2640
Lime and shale	2640	4148
Lime	4148	4318
Sand Lime	4318	4338
Lime	4338	4370
Lime and shale	4370	4403
Lime	4403	4575
Lime Cherty & Shale	4575	4599
Shale and lime	4599	4761 Total depth

I, Don S. Packer, hereby certify that the above Log is true and correct to the best of my knowledge and belief.



Subscribed and sworn to before me this 30th day of July, 1951.



Notary Public

My commission expires: March 22, 1952

**PLUGGING**  
 FILE SEC 34 T 21 R 34W  
 BOOK PAGE 86 LINE 4

**RECEIVED**  
 STATE CORPORATION COMMISSION

AUG 1 1951

SHALLOW WATER  
 GARDEN CITY

**RECEIVED**

JUL 31 1951

AM PM  
 7 8 9 10 11 12 1 2 3 4 5 6