

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20,060-0000

LEASE NAME Fleagle

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER "A" #1

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 11 TWP. 21 RGE. 34 (E) or (W)

COUNTY Finney

Date Well Completed _____

Plugging Commenced 4-11-88

Plugging Completed 4-15-88

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS Box 97, Ellinwood, Ks. 67526

PHONE# (316-564-2577) OPERATORS LICENSE NO. 5131

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4874

Show depth and thickness of all water, oil and gas formations.

STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

4-19-88
APR 19 1988

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	420'	None
				5-1/2"	4737'	741.65'

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4300' and 5 sacks cement. Shot casing at 3500', 2500', 1500', 1200', 900' and 700'. Pulled 21 joints of 5-1/2" casing. Allied squeezed well with 3 sack hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 120 sacks lite cement. Maximum pressure was 800 psi and shutin 350 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 18th day of April, 19 88

Iona M. Leatherman
Notary Public

My Commission Expires:

