


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hamilton County, Sec. 23 Twp. 21 Rge. 41 (W)

Location as "NE/CNW&SW&" or footage from lines SE/NW (Approx)
Lease Owner Kansas-Nebraska Natural Gas Co., Inc.
Lease Name Martin Well No. 1-D
Office Address 300 N. St. Joseph Street, Hastings, Nebraska
Character of Well (completed as Oil, Gas or Dry Hole) Disposal
Date well completed 3-4 19 71
Application for plugging filed 10-2 19 72
Application for plugging approved 10-12 19 72
Plugging commenced 11-10 19 72
Plugging completed 11-10 19 72
Reason for abandonment of well or producing formation Adjacent gas well
abandoned.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves
Producing formation Glorietta Depth to top 1416 Bottom 1520 Total Depth of Well 1629 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Glorietta	Water	1416	1520	2-7/8	1629	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Mixed and pumped 15 sks cement for plug at 1520 to 1120. Cement down with fresh gel mud. 2 sks put in for top plug 60' to 0.

12-5-72
RECEIVED
STATE CORPORATION COMMISSION
DEC 5 - 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargent Casing Pulling Service,
Address Liberal, Kansas

STATE OF KANSAS, COUNTY OF KEARNY, ss.
Lawrence Holmstrom (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence Holmstrom
Lakin, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 72
Olive H. Shean
Notary Public.

My commission expires Dec. 27, 1973

CONTRACTOR'S WELL LOG

OPERATOR: Kansas-Nebraska Natural Gas
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: #1-D MARTIN "Twin"
 LOCATION: 1980' FWL, 2590' FNL
 Sec. 23-21S-41W, Hamilton Co., Ks.
 GEOLOGIST:
 SPUD DATE:
 COMPLETION DATE: December 11, 1970

0	65	Rock
55	130	Clay
130	210	Sand
210	220	Shale
220	1219	Shale & Shells
1219	1635	Shale
	1635	Rotary Total Depth

Ran 2-7/8" tubing set at 1624' w/200 sx. posmix. Plug was down at 8:00 p.m. 12-11-70.

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 12 1972
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the #1-D MARTIN "Twin", 1980' FWL, 2590' FNL, Sec. 23-21S-41W, Hamilton County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr
 President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 15th day of December, 1970.

Sue J. McCoy
 Sue J. McCoy, Notary Public

My Commission Expires:
 November 12, 1973