


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Stafford County. Sec. 5 Twp. 23 Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines NW SE NE
Lease Owner Natural Gas and Oil Corp & Sinclair Oil & Gas Co
Lease Name Holbrook Well No. 1
Office Address 1009 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed July 9, 1953 19
Application for plugging filed July 9, 1953 (Orally) 19
Application for plugging approved July 10, 1953 (written) 19
Plugging commenced July 9, 1953 19
Plugging completed July 9, 1953 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	200	10 3/4"	200	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 4090 to 200 feet
Set plug at 200 feet and ran 20 sacks cement to 140 feet
Filled with heavy mud from 140 to 20 feet
Set plug and ran 10 sacks cement to cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Drilling Department of Natural Gas and Oil Corporation
Address 1009 Central Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Harold A. Burt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold A. Burt
1009 Central Building, Wichita 2, Kans (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 53

Esther Twissell
Notary Public.

My commission expires May 25, 1957

24-7368-8 3-53-20M

PLUGGING RECORD
WICHITA, KANSAS
JULY 13 1953

RECEIVED
7-15-53
DIVISION
KANSAS

15-185-00137-0000

DRILLERS LOG

COMPANY: Natural Gas and Oil Corporation and
Sinclair Oil and Gas Company

LOCATION: Holbrook #1 NE SE NW Section 5-23S-14W
Stafford County, Kansas

CONTRACTOR: Drilling Department-Natural Gas & Oil Corp

COMMENCED: June 23, 1953

COMPLETED: July ;9, 1953

ELEVATION: 1967 DF

0 to 115 Sand
 115 to ; 200 Shale
 200 to 340 Shale and shells
 340 to 420 Sand
 420 to 870 Red bed
 870 to 912 Anhydrite
 912 to 1375 Shale and shells
 1375 to 1500 Shale-salt and shells
 1500 to 1680 Shale and shells
 1680 to 1925 Lime and shale
 1925 to 2090 Lime
 2090 to 3345 Lime and shale
 3345 to 3399 Lime
 3399 to 3402 Shale
 3402 to 3456 Lime and shale
 3456 to 3460 Shale
 3460 to 3501 Lime and shale
 3501 to 3549 Shale
 3549 to 3554 Lime
 3554 to 3561 Shale
 3561 to 3794 Lime
 3794 to 3900 Shale and lime
 3900 to 3925 Shale-lime-chert
 3925 to 3942 Chert
 3942 to 3981 Chert and lime
 3981 to 3983 Lime
 3983 to 4000 Shale and sand
 4000 to 4010 Sand
 4010 to 4054 Shale and sand
 4054 to 4090 Lime and shale
 4090 T. D. (RB)

Set 200' of 10 3/4" surface pipe . Cemented with 225 sacks cement and 3 sacks cal. chloride.

TOPS:	Anhydrite	867	Lansing	3558	Viola	3907
	Heebner	3413	Base KC	3786	Simpson	3986
	Brown Lime	3545	Cherty Cong	3873	Arbuckle	4034
			Shaley Cong	3888		

Drill Stem Tests:

- #1 3675-97, op 1 hr, good blow, rec. 900' gas, 90' OCM, 130# BHP
- #2 3709-3737, open 1 hr, weak blow 2 min, rec. 5' mud, 54# BHP
- #3 3925-55, op 1 hr, rec. 3' mud, 0 BHP , weak blow 6 min.
- #4 3969-4007, op 1 hr, rec 150' gas, 90' sl O&GCM, 0 BHP

Schlumberger run
 DRY, PLUGGED AND ABANDONED

C E R T I F I C A T E

I, Harold A. Burt, do hereby certify that the above and fore-going is a true and correct copy of the log of the Holbrook #1 NW SE NE Sec- 5-23-14W, Stafford County, Kansas as reflected by files of the Natural Gas and Oil Corporation.

JUL 15 1953

CONSERVATION DIVISION

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 14th day of July, 1953.

My Commission expires May 25, 1957

Harold A. Burt
 Harold A. Burt

Esther Unsell
 #Esther Unsell, notary public

