


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County. Sec. 33 Twp. 21S Rge. 25W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-SE NE

Lease Owner Tomlinson Oil Co., Inc.
Lease Name Sinclair Well No. 1
Office Address 200 W. Douglas Suite 1030 Wichita Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plat

Date Well completed August 22, 1977
Application for plugging filed Verbal Application 1977
Application for plugging approved Verbal Approval 1977
Plugging commenced August 22, 1977
Plugging completed August 22, 1977
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,608'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	307'	None
	8-31-77					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,608 ft. (rotary total depth) to 900 ft. Set plug at 900 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 900 ft. to 300 ft. Set plug at 300 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 15 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting - Agent (Signature of owner) or (Notary Public)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 30th day of August, 1977

Elsie Willison
Elsie Willison - Notary Public.

My commission expires June 30, 1978

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Tomlinson Oil Co., Inc.

SEC. 33 T. 21S R. 25W
LOC C-SE NE

FARM Sinclair


NO. 1

COUNTY Hodgeman

TOTAL DEPTH 4,608'
COMM. August 13, 1977

COMP. August 22, 1977

SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED August 30, 1977



CASING		ELEVATION	PRODUCTION
20	10'	2,465 K.B.	
15	8 5/8" 307' cemented w/200 szs cement		
12	6		
13	5		

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	1,681'
Anhydrite	1,715'
Shale	2,400'
Shale and Lime	3,320'
Lime and Shale	3,997'
Lime	4,608'
Rotary Total Depth	4,608'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

RECEIVED
WELL COMMISSION COMMISSION

H-30, Inc.


AUG 31 1977

CONSERVATION DIVISION
Wichita, Kansas

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss

Subscribed and Sworn to before me a Notary Public in and for said county and state this 30th day of August, 1977



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
June 30, 1978