

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-093-20037-0001

LEASE NAME Miller "A"

WELL NUMBER #1

SPOT LOCATION C- NE- SE

SEC. 32TWP. 21RGE. 35(2) or (W)

COUNTY Kearny

Date Well Completed 11-15-72

Plugging Commenced 2-14-1985

Plugging Completed 2-19-1985

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Maurice L. Brown Co.

ADDRESS 200 Sutton Pl. Bldg.

PHONE #(316) 265-4651 OPERATORS LICENSE NO. 6234

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Marm. (Johnson) Depth to top 4544 bottom 4557 T.D. 5065

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	366'	0'
Production				5 1/2"	4602'	955'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls & 20 sks. cement to 4400' and pressured to 700 lbs. Shot pipe @ 955' & layed down 2 jts. 400' & pumped 40 sks. cement 400' to 300'. Cut off 8 5/8", 3 1/2' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

3-12-85

RECEIVED

STATE OF KANSAS COUNTY OF HASKELL, ss.

STATE CORPORATION COMMISSION

I, Edgar J. Eves

(XXXXXXXXXXXXXXXXXXXX) or

MAR 12 1985

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) Edgar J. Eves

(Address) Box F, Sublette, KS. 67877

SUBSCRIBED AND SWORN TO before me this 25th day of Feb., 1985

Sandra L. Eves
Notary Public



My Commission expires: 12-6-88

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

MILLER #1 OWWO
C NE SE, Section 32-21S-35W
Kearny County, Kansas

Old Information: Operator: Abercrombie Drilling Co.
Spud: 7/10/1972
T.D. 5065'
D & A: 7/26/72

New Information:

Commenced: October 23, 1972
Completed: October 27, 1972

OPERATOR: MAURICE L. BROWN

Depth		Formation	Remarks
From	To		
0	50	Cement	Ran 366' of 8 5/8" csg. cemented w/250 sks cement (was Abercrombie Drilling Co. Miller #1)
50	4763	Open hole	
4763	TD		
			Ran 149 jts of 5 1/2" csg. set @ 4602' cemented w/165 sks Posmix 65% Class H 35% Pozalen 2% Gel 10% Salt 3/4% of CFR-3, Glosote 1/2# Tuffiber P.D. @ 12:05 AM 10/27/1972 Job by Howco

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE SE, Section 32-21S-35W, Kearny County, Kansas, to the best of my knowledge and belief.


James S. Sutton, II
James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1985

Before me, the undersigned, a Notary Public, within and for said County and State, on this 10th day of November, 1972, personally appeared James S. Sutton, II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.



Marjorie Hall
Marjorie Hall, Notary Public