



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

12-27-65  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1965  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Leben of Shallow Water Ref. Co. has this date requested permission to plug the following described well:

Mr. Leben guarantees payment of the plugging fee.

Operator's full Name: Shallow Water Ref. Co.

Complete Address: 325 Wichita Plaza, Wichita, Kansas

Lease Name: Scheverman Well No. # 1

Location: C SW NE Sec. 28 Twp. 21S Rge. 35 (E) (W)

County Kearney Total Depth 5075' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Leben was instructed to plug the well as follows:

- 8 5/8"-400' Circulated w/cement.
- Mud 5075' to 650' Spotted 25 Sax. cement 650' to 575'
- Mud 575' to 400' Spotted 25 Sax. cement 400' to 325'
- Mud 325' to 45' Plug, Hulls, 15 Sax. cement 45' to 0

Very truly yours,

*FHugh Scott*  
Conservation Division Agent