



15-009-15691-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas

05-18-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Earl Backer of Nat'l. Coop. Ref. Assoc. has this date requested permission to plug the following described well:

Mr. Nat'l. Coop. Ref. Assoc. guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association

Complete Address: P. O. Box # 6, Great Bend, Kansas 67530

Lease Name: Depiesse Well No. # 5

Location: SE NE SE Sec. 6 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3288 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Ralph Comstock was instructed to plug the well as follows:

8 5/8" csg. 375'. No cement. Perf. 3090'.

Sanded hole back to 3000' & dumped 5 sax cement with dump bailer.

Pulled pipe. Circulated hole with mud @ 240' & displaced 100 sax

cement thru pipe @ 220'. Pulled pipe to 40' & displaced 50 sax cement

thru pipe with Allied Cementing Company's pump truck, cementing to

base of cellar.

Very truly yours,

Don Lusk  
Conservation Division Agent