



15-009-15689-0990

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas

7-28-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. W. F. Griffith of Nat'l. Coop. Refinery Assoc. has this date requested permission to plug the following described well:

Mr. Nat'l. Coop. Refinery guarantees payment of the plugging fee. Association.

Operator's full Name: National Cooperative Refinery Association

Complete Address: Box 6, Great Bend, Kansas 67530

Lease Name: NW Beaver Unit (Depiess) Well No. Tract 8 # 3

Location: NE NE SE Sec. 6 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3275 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Earl Baker was instructed to plug the well as follows:

7" 352' with mud.

No pipe recovery. Well previously squeezed. Run tubing to 3000' &

displaced 40 sax cement. Displaced 15 sax mud thru tubing. Pulled

tubing to 550' & displaced 30 sax cement. Pulled remaining tubing

& displaced 10 sax cement with Globe Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don L. Brown  
Conservation Division Agent