



15-083-20413-0000

called
4:30 pm
4 Jan - 1975

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

*Intentions to drill issued
Dec-16th 1974 - 15-083-20,143. 1-6-75*

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1975

CONSERVATION DIVISION
WICHITA, KANSAS

Dear Sir:

Mr. Fred Cameron of H-30 Inc. has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Jack Bowles

Complete Address: 410 Local Federal Bldg, Okla City, Okla

Lease Name: Wright "31" Well No. #1

Location: N.W. N.W Sec 31 Twp. 21 Rge. (E)(W) ~~W~~

County: Hodgeman Total Depth 4600 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

*There was 271 ft of 8 1/8 set with 250
sacks of cement. First plug at 850 ft
with 60 sacks of cement. Filled with
heavy mud to 550 ft. 35 sack of cement.
Fill with heavy mud and 15 sacks
of cement from 450 ft.
1 sack in rat hole*

Very truly yours,

Charles F. Thomas
Conservation Division Agent