



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Lacy of Beardmore Drlg, Co. has this

date requested permission to plug the following described well:

Mr. Lacy guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drlg., Co.,

Complete Address: 700-120 Bldg., Wichita, Kansas

Lease Name: Wright "B" Well No. 2

Location: NWNE Sec. 31 Twp. 21 Rge. 24 (E) (W)

County: Hodgeman Total Depth 4580' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Lacy was instructed to plug the well as follows:

8 5/8" to 523' circulated w/ cement. Mud 4580' to 720'

Spotted 70 sacks cement 720' to 500' Mud 500' to 480'

Plug & 20 sacks cement 480' to 420' Mud 420' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

10-14-68

Very truly yours,

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 14 1968

CONSERVATION DIVISION  
 Wichita, Kansas

*Edward Eves*  
 Conservation Division Agent