



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

10-9-73

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clark of Jack Bowles has this

date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Jack Bowles

Complete Address: 401 Local Federal Bldg., Oklahoma City, Oklahoma

Lease Name: Wright Well No. 1

Location: C N/2 SW Sec. 30 Twp. 21 Rge. 24 ^{XX}(E)(W)

County: Hodgeman Total Depth 4605' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

8 5/8" to 369' circulated w/ cement. 5 1/2" to 4604' cemented.

Top perforations 4530' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4500' Mud 4500' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 350'

Spot 30 sacks cement 350' to 250' Mud 250' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent