



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

7-15-70

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Steincapp of R.V. Lehner has this

date requested permission to plug the following described well:

Mr. Steincapp guarantees payment of the plugging fee.

Operator's full Name: R.V. Lehner

Complete Address: Box 398, Ness City, Kansas

Lease Name: Bieber Well No. 2

Location: C SE SE Sec. 30 Twp. 21 Rge. 24 ^{XX}(E)(W)

County: Hodgeman Total Depth 4550' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincapp was instructed to plug the well as follows:

- 8 5/8" to 288' circulated w/ cement. Mud 4550' to 900'
- Spot 80 sacks cement 900' to 600' Mud 600' to 280'
- Spot 30 sacks cement 280' to 180' Mud 180' to 40'
- Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edward J. Eves
Conservation Division Agent