



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 30 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

9-30-68

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Reimert of Champlin Petro. Co. has this

date requested permission to plug the following described well:

Mr. Reimert guarantees payment of the plugging fee.

Operator's full Name: Champlin Petroleum Company

Complete Address: Box 308, Ellinwood, Kansas

Lease Name: Bamberger Well No. 1

Location: C NW NW Sec. 25 Twp. 21 Rge. 23 (E) (W)

County: Hodgeman Total Depth 4570' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reimert was instructed to plug the well as follows:

8 5/8" to 275' ciru. W/ cement. 4 1/2" to 4569' ciru. w/ cement

Top perforations 4546' Mud 4546' to 3814'

Spot 10 sacks cement 3814' to 3669' Mud 3669' to 900'

Spot 25 sacks cement 900' to 434' Mud 434' to 270'

Spot 10 sacks cement 270' to 125' Mud 125' to 75'

Plug & 5 sacks cement 75' to 0'.

Very truly yours,

Conservation Division Agent