



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

2-27-73

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Steincamp of Al Tipton has this

date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Al Tipton

Complete Address: Box 157, Hays, Kansas

Lease Name: Stairett Well No. 1

Location: C SW Sec. 18 Twp. 21 Rge. 23 (E) (W)

County: Hodgeman Total Depth 4530' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Steincamp was instructed to plug the well as follows:


8 5/8" to 329' circulated w/ cement. Mud 4530' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 320'

Spot 30 sacks cement 320' to 220' Mud 220' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent