



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-185-30108-0000

RECEIVED  
STATE CORPORATION COMMISSION

AUG 17 1965

CONSERVATION DIVISION  
Wichita, Kansas

8-17-65

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Johnnie Crow of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Crow guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Batchman Well No. # 1

Location: SE NW NE Sec. 9 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 3547' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Crow was instructed to plug the well as follows:

213' of 8 5/8" surface pipe, cement circulated with 250 sacks.  
Fill hole with drilling mud to 200', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

*Archie Elving*