



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-185-12112-0001

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1962

CONSERVATION DIVISION
Wichita, Kansas

12-4-62

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Nov. 26, 1962

Dear Sir:

Mr. Raymond Hubbard of R & D Caseing Pulling Co. has this
 date requested permission to plug the following described well:

Mr. Raymond Hubbard guarantees payment of the plugging fee.

Operator's full Name: National Drilling Co.

Complete Address: 531 Petroleum Bldg. Wichita, Kansas.

Lease Name: Welch #1 Well No. #1

Location: NW-SW-SE Sec. 9 Twp. 23 Rge. 14 (E) (SW) X

County Stafford County Total Depth 4060' Oil Well X
 abandoned.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Raymond Hubbard was instructed to plug the well as follows:

4028' of 4 1/2" long string cemented with 140 sacks cement,
plugged at 3765'. Top perforation at 3748'. sanded to 3730'
& 3 sacks cement. Hole filled to 200' with mud, 10' rock
bridge and 20 sacks cement. Hole filled to 40' with mud,
10' rock bridge and 10 sacks cement to base of cellar.

Very truly yours,

Harmon Justice
 Conservation Division Agent