

6-16-88

218R

To: 6 070690
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-151896-000
S/2 SW SE, SEC. 6, T 16 S, R 12 W/2

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name N. W. Beaver Well # T 8 - W 1
Depiesse

Operator: National Cooperative Refinery ASS@ County Barton
Name& Address: Box 6
Great Bend, Ks. 67530

107.90

Well Total Depth 33200 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 10 feet 555

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Box 31 Russell, Ks. 67665

Company to plug at: Hour: 1:00 PM Day: 16 Month: June Year: 19 88

Plugging proposal received from Jim Rockhold and Jim Baker

(company name) Rockhold Eng. and N.C.R.A. (phone) _____

were: 10" - 555' S.P. cwc w/NA 5 1/2" casing at 3314' w/N.A. Perferated 2876' to 3214'.

At bottom sand to 2825' and w/5 sks cement. Shot casing 5 times. Recovered 1745'.

Proposal 200 sks 65/35 Poz 10% Gel 2% Additive. Pump in with pump truck. Pump in 25 sks cement followed with 175 sks cement w/5 sks Hulls. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45PM Day: 16 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Ordered 200 sks 65/35 Poz 10% Gel 2% Additive and 5 sks Hulls.

Pumped in with pump truck. Pumped in 25 sks cement followed with 175 sks cement

w/5 sks Hulls added in. Max pressure 400 Psig. Shut in pressure 150 Psig. Cemented

by Allied Cement.

STATE CORPORATION COMMISSION

07-06-88 JUN 16 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
Please conserve this plugging.

Signed Marion J. Schmidt (TECHNICIAN)
Marion J. Schmidt

DATE 7-13-88

INV. NO. 21282