

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-10188-00-00  
Spot: SWSE Sec/Twnshp/Rge: 13-21S-24W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: GOEBEL EAST UNIT Well Number: H-2  
County: HODGEMAN Total Vertical Depth: 4489 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 SOUTH MAIN - SUITE 505  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 205 WITH 155 SX CMT  
Production: Size 5.5 feet: 4488 WITH 100 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_ \$145.89

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2001 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 4410' & 4 SX CMT. 1ST PLUG AT 700' WITH 80 SX CMT. 2ND PLUG AT 220' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER  
Date/Time Plugging Completed: 07/17/2001 10:00 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4481'. PERFS AT 4466-76'. SANDED TO 4410' & 4 SX CMT. PERFORATE AT 700' PUMPED 80 SX CMT. SPOTTED 40 SX CMT AT 220' WITH CASING. SPOTTED 20 SX CMT FROM 0-40'.

RECEIVED  
KANSAS CORPORATION COMMISSION  
8-1-01  
AUG 01 2001  
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 240' OF 5 1/2" CASING.

Plugged through: CSG

INVOICED  
DATE 8-01-01  
INV. NO. 2002080154

District: 01

Signed Michael Maier  
(TECHNICIAN)

JUL 18 2001

Form CP-2/3