

To: 1051879 12-29  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA  
W/2 NE SE, SEC. 13, T. 21 S, R. 24 W/E  
1980 feet from S section line  
810 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123  
Operator: Pickrell Drilling Co., Inc.  
Name & Address 110 N. Market, Ste. 205  
Wichita, KS 67202

Lease Name Goebel East Unit Well # H-4  
County Hodgeman  
Well Total Depth 4496 146.12 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mikes Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 9:30 a.m. Day: 29 Month: 12 Year: 19 94

Plugging proposal received from Vernon Duntz Jr.

(company name) Mikes Testing & Salvage Inc. (phone) 316-938-2943

were: 4 1/2" at 4479' w/100 sx cement. Open hole 4479-4496'

1st plug sand back to 4425' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1600', 3rd plug pump 80 sx cement at 700',

4th plug pump 40 sx cement at 300', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45 a.m. Day: 29 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4425' and dumped 4 sx cement top of sand through bailer,

Shot hole in the 4 1/2" at 700'.

2nd plug pumped 100 sx cement down the 4 1/2" casing. Maximum pressure 400 psi and shot in 50 psi.

3rd plug pumped 100 sx cement down 8 5/8" X 4 1/2" annulus. Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. 1-4-98  
(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED  
DATE 1-9-95  
INV. NO. 42023

Signed Richard W. Lacey  
(TECHNICIAN)

STATE RECEIVED  
CORPORATION COMMISSION  
JAN 9 4 10 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS