

1 050799

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-20,054A

NW NE, SEC. 31, T 21 S, R 24 (W/E)
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Wright "CB" Well # 1

Operator: Phillips Petroleum Co.
Name & Address: Rt. 3, Box 20-A
Great Bend, KS 67530

County: Hodgeman 148.85

Well Total Depth 4580 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 524

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 pm Day: 21 Month: April Year: 19 86

Plugging proposal received from Roger Lust

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4577' PBD 4491' Perfs at 4484-4489'

1st plug sand back to 4430' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 21 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4430' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 100 psi

Remarks: Recovered 2400' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BI-Titan.
(if additional description is necessary, use BACK of this form.)

INVOICED
(if additional description is necessary, use BACK of this form.) observe this plugging.

DATE APR 29 1986

INV. NO. 13595

Signed Richard W. Lucey (TECHNICIAN)

STATE CORPORATION COMMISSION
APR 28 1986
CONSERVATION DIVISION
WICHITA, KANSAS