

1050832

15-083-20175-0000

113 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

DOCKET NO. D-16,284
API NUMBER 15-083-20,175
C SW NE, SEC. 30, T 21S S, R 24 W/KX
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Bieber Well # 1 (SWD)

Operator: Okmar Oil Company

County Hodgeman 149.01

Name & Address 670 Fourth Financial Center

Well Total Depth 4585 feet

Wichita, Kansas 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 506

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number None

Address _____

Company to plug at: Hour: 11:30 am Day: 11 Month: July Year: 1986

Plugging proposal received from Ted Crawford

(company name) _____ (phone) (913) 628-6101

were: to fill hole with heavy mud and to spot cement through drill pipe

5 1/2" at 1420' PBTD 1420' Perfs at 1258-1332'

1st plug spotted cement at 1420'

2nd plug spotted cement at 500'

3rd plug spotted cement to surface

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:15 pm Day: 11 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug pumped 150 # Hulls and then 70 sx Thrifty Mix ~~down~~

STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

5 1/2" casing with 100 # Hulls mixed in.

7-21-86

JUL 21 1986

Maximum pressure 1000 psi and shut in 900 psi.

Remarks: No casing was recovered. Used 65/35 Poz with 10% Gel and 2% A2 by B. J. Titan.
(If additional description is necessary, use BACK of this form.)

~~(copy to file)~~ Observe this plugging.

DATE JUL 23 1986

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 14429

7-11