

1 020057

FEB 8 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,273-0000
Approx. SW SE SE, SEC. 32, T 21 S, R 23 W/E
380 feet from S section line
825 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8890

Lease Name Bradshaw Well # 1-32

Operator: Donald J. Malone, Geologist
Name & Address 919 Century Plaza Bldg.
Wichita, KS 67202

County Hodgeman 151.94

Well Total Depth 4675 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 588

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 KS State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 3:30 a.m. Day: 8 Month: 2 Year: 1987

Plugging proposal received from Mike Waggoner

(company name) Red Tiger Drilling Company (phone) 913-625-7966

were: to fill hole with heavy mud and spot cement through drill pipe. Anhydrite 1604'

1st plug at Base Anhydrite with 50 sx cement,

2nd plug at 30' below the base of surface pipe with 50 sx cement,

3rd plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 8 Month: 2 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 1604' with 50 sx cement,

2nd plug at 618' with 50 sx cement,

3rd plug solid bridge plug with 1 sx hulls and plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

2-12-87

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED

DATE 2-16-87

INV. NO. 16125

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date .. January 15, 1987 .. month day year

API Number 15- 083-21,273 yes

OPERATOR: License # 8890
Name .. Donald J. Malone, Geologist
Address .. 919 Century Plaza Bldg
City/State/Zip .. Wichita, Kansas 67202
Contact Person .. Don Malone
Phone .. 316-2634225 or 683-4428

Sec. 32 Twp. 21 S, Rg 23
380 Ft. from South Line of Section
825 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302
Name .. Red Tiger Drilling
City/State .. Wichita, Kansas

Nearest lease or unit boundary line 380 feet
County .. Hodgeman
Lease Name .. Bradshaw Well # 1-32
Ground surface elevation NA 7 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water 500 ft
Depth to bottom of usable water 500 ft Kd
Surface pipe by Alternate: 1 x 2
Surface pipe planned to be set 525 ft
Conductor pipe required None
Projected Total Depth 4750 feet
Formation .. Mississippian

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 12-18-86 Signature of Operator or Agent Donald Malone Title Geologist

For KCC Use:

Conductor Pipe Required .. feet; Minimum Surface Pipe Required 525 feet per Alt. 1 8
This Authorization Expires 6-29-87 Approved By 12-29-85

Move in 1-29-87 set 575' of 8 3/8

Sec. Twp. S, Rg. East West

Top Permian @ ~700'

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1000 Base only - 50 feet depth with 20 sxs of Com. man
2nd plug @ 500 30' below surface - 60 feet depth with 30 sxs of
3rd plug @ feet depth with sxs of
4th plug @ feet depth with sxs of
5th plug @ feet depth with sxs of
(2) Rathole with 10 15 sxs (b) Mousehole with sxs

PUSHER Mike Wagner
TD 4675 FORMATION Miss
SURFACE PIPE 8 3/8 @ 588'
ANHYDRITE 1604 ELEVATION
STARTING TIME & DATE 3:30 AM 2-28-87
COMPLETION TIME & DATE 4:20 AM
1st PLUG @ 1604 FT. W/ 50 SX
2nd PLUG @ 618 FT. W/ 20 SX
3rd PLUG @ plug @ 470' into section w/ 15' hole FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied 60/40 for 690
TECHNICIAN

STATE CORPORATION COMMISSION

FEB 12 1987

CONSERVATION DIVISION