

1 080481

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21,104-6000

NE SW NW, SEC. 8, T 23 S, R 14 W/E

3630 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Snyder Well # 3

Operator: F & M Oil Co., Inc.

County Stafford 121.36

Name & Address 422 Union Center

Well Total Depth 3734' feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 476

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:45 am Day: 7 Month: February Year: 19 86

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3729' Open Hole 3728-35'; Perfs at 3724-27'; 3688-94'

1st plug sand back to 3630' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 140 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 pm Day: 7 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3630' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 140 sx cement.

2/17/86

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 600 psi and shut in 200 psi

FEB 17 1986

Remarks: Recovered 2800' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied Conservation Division  
(if additional description is necessary, use BACK of Form 15, Form 15, Wichita, Kansas)

**INVOICED**

(XXXXXX) observe this plugging.

DATE 1-17-86

Signed J. N. McJ  
(TECHNICIAN)

INV. NO. 12614