

1 080483

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE NE NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,801-0000
_____, SEC. 8, T 23 S, R 14 W/8

4290 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Snyder Well # 2

Operator: F & M Oil Co., Inc.

County Stafford 132.63

Name & Address 422 Union Center
Wichita, KS 67202

Well Total Depth 4081 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 458

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 7 Month: February Year: 19 86

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4080' PBT 4028' Perfs at 3688-93'; 3787-90'

1st plug sand back to 3630' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 140 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 7 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3630' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 140 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 600 psi and shut in 350 psi

FEB 17 1986 2-17-86

Remarks: Recovered 3000' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK SHEET(S) PROVIDED)

INVOICED

DATE 2-17-86

Signed J. H. [Signature] (TECHNICIAN)

INV. NO. 12626