

1 080482

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,721-6000

NW SE NW , SEC. 8 , T 23 S, R 14 W/E  
3630 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Snyder Well # 1

Operator: F & M Oil Co., Inc.

County Stafford 132.63

Name & Address 422 Union Center

Well Total Depth 4081 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 am Day: 7 Month: February Year: 19 86

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3870' PBD 3787' Perfs at 3722-32'; 3684-90'

1st plug sand back to 3630' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 140 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:20 am Day: 7 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3630' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 140 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 750 psi and shut in 250 psi

2-17-86 FEB 17 1986

Remarks: Recovered 2800' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK OF THIS FORM)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 1-17-86

Signed J. H. [Signature] (TECHNICIAN)

INV. NO. 12615