

To: 1 121105
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Operator: L.D. Drilling, Inc.

Name & Address Rt. 1, Box 183 B

Great Bend, KS 67530

API NUMBER 15- 185-22,239-8000
SW NW SE, SEC. 9, T 23 S, R 14 W/E
1650 feet from S section line
2310 feet from E section line

Lease Name Welsh Well # 1

County Stafford

Well Total Depth 4050 131.63 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1 p.m. Day: 8 Month: 2 Year: 19 96

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

was: 4 1/2" at 4049' w/175 sx cement, Perfs at 3362-67, 3701-07, 3963-70, 3973-77'

1st plug sand back to 3310' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 8 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3310' and dumped 4 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement. 2-12-96

Pumping pressure 0-500 psi and shut in 200 psi.

KANSAS CORPORATION COMMISSION

FEB 12 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2340' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form. CONSERVATION DIVISION WICHITA, KS)

Observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED

DATE 2-27-96

INV. NO. 44894