

1 080580

Plugged 12-12-86

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,554-6000
SW SW NE, SEC. 9, T 23 S, R 14 W/R
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers Inc. of Kansas
Name & Address Box 8647
Wichita, KS 67208

Lease Name Walls Well # 4
County Stafford 131.63
Well Total Depth 4050 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 12 Month: 12 Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4049' BPTD 4004' Perfs at 3962-78, 3914-26, 3748-51, 3710-14, 3668-74'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 10 sx gel, 2 sx hulls, and 150 sx ATL cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4 p.m. Day: 12 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 10 sx gel, 2 sx hulls, and 150 sx ALC cement.

12-18-86

DEC 18 1986

CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 700 psi and shut in 30 psi.

Remarks: Used ALC cement by Allied. Recovered 2051' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

~~did not~~ observe this plugging.

Signed J. M. [Signature]
(TECHNICIAN)

INVOICED
DATE 1-2-87
INV. NO. 15708