

1 010040

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,450-~~6000~~
NW SE, SEC. 9, T 23 S, R 14 W/E
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers, Inc. of Kansas
Name & Address: P. O. Box 8647
Wichita, KS 67208

Lease Name R. J. Welsch Well # 2
County Stafford
Well Total Depth ~~4050~~ 4005 130.116 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 314

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 24 Month: October Year: 19 85

Plugging proposal received from Brad Siroky

(company name) Oil Producers (phone) 316-682-3022

were: 4 1/2" at 4049' PBTD 4005' Perfs at 3960-80'

- 1st plug sand back to 3910' and dump 4 sx cement on top of sand through bailer
- 2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
- release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 am Day: 24 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Plugged water well with 10 sx cement.

Maximum pressure 500 psi and shut in 100 psi

Remarks: Recovered 2000' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
observe this plugging.

NOV 1 1985

Signed *Paul A. Luthi* (TECHNICIAN)

DATE 11-1-85

INV. NO. 10869

CONSERVATION DIVISION
Wichita, Kansas

11-1-85