

1 060813

API NUMBER 15-185-21,147-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NW, SEC. 9, T 23 S, R 14 W
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Harper Well # 1

Operator: L. D. Drilling, Inc.
Name & Address P. O. Box 324
Great Bend, KS 67530

County Stafford 130.98
Well Total Depth 4030 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 3:00 pm Day: 26 Month: February Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4029' Perfs at 3953-70'

1st plug sand back to 3900' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:40 pm Day: 26 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 500 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2032' 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

~~INVOICED~~ observe this plugging.

MAR 04 1986

STATE CORPORATION COMMISSION

Signed Paul A. Luthi
(TECHNICIAN)

DATE _____

MAR 4 1986

3-484

INV. NO. 12861

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84