

1 080590

API NUMBER 15-185-21,107-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW NW NE , SEC. 9 , T 23 S, R 14 W/E

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Walls Well # 1

Operator: Oil Producers Inc. of Kansas

County Stafford 130.81

Name & Address Box 8647

Well Total Depth 4025 feet

Wichita, KS 67208

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 30 Month: 12 Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4024' PBDT 3990' perfs at 3956-72', 3914-28', 3670-74'

1st plug sand back to 3600' and dump 4 sx of cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 10 sx gel, 2 sx hulls, and 150 ATL cement.

Plugging Proposal Received by Don Ubel and Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 a.m. Day: 30 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 15 sx gel, 2 sx hulls, and 150 sx cement. (ALC)

STATE CORPORATION COMMISSION

1-6-87

JAN 6 1987

CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Recovered 2018' of 4 1/2" casing. Used ALC cement by Allied.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 1-7-87

Signed J. M. [Signature]  
(TECHNICIAN)

INV. NO. 15822