

1 120069

2-15-88

129 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185 12111-00-01
SW SE NE, SEC. 9, T 23 S, R 14 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling
Name & Address: Rt. 1, Box 183B
Great Bend, KS 67530

2970 feet from S section line
990 feet from E section line
Lease Name Walls Well # 1 OWWO
County Stafford
Well Total Depth 4075 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 423

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 15 Month: 2 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4058' Open hole Shot at 3412, 3207, 3000, 2608, 2388, 2191'

1st plug sand back to 4000' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 5 sx hulls and 125 sx ATL cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 15 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 4 sx cement on top
of sand through bailer,

2nd plug pumped in 8 5/8" with 500 lbs. hulls and 125 sx ATL cement.

Pumping pressure 500 psi and shut in pressure 100 psi.

Remarks: Used ATL cement by Allied. Recovered 2115' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
If a check is received observe this plugging.

Signed *Steve Durrant* (TECHNICIAN)

DATE 2-29-88

INV. NO. 19936