

To: 1 120501  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-4  
API NUMBER 15-185-22,682-6006

W/2 SW NE, SEC. 14, T 23 S, R 14 W/E

3280 feet from S section line

2200 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30326

Lease Name Smith Well # 1

Operator: Howard Williford

County Stafford 130.94

Name & Address Rt 1, Box 35

Well Total Depth 4029 feet

Alden, KS 67512

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 4 Month: 12 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4021' w/150 sx cement, PBTB 3700', Perfs at 3646-85' (2 sets)

1st plug sand back to 3600' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 500 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45 a.m. Day: 4 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3650' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel, 150 lbs. hulls and 100 sx cement.

Plate with 4 1/2" collar welded on top of surface casing.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2604' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

1  INVOICED observe this plugging.

DATE 1-7-91

INV. NO. 30379

Signed Steve Pfeifer  
(TECHNICIAN)