

To: 1 040597  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-2  
API NUMBER 15-185-20,102-6000  
100' N & 100' E  
of C SW SW, SEC. 15, T. 23 S, R. 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30517

Operator: Turnco Drilling Inc.

Name & Address P.O. Box 771327

Wichita, KS 67277-1329

760 feet from S section line

4520 feet from E section line

Lease Name George Walls Well # 1

County Stafford 131.23

Well Total Depth 4038 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 p.m. Day: 2 Month: 12 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4033', PBTD 4020', Perfs at 3969-84'

1st plug sand back to 3910' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 20 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 2 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3919' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 20 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 650 psi and shut in 150 psi.

RECEIVED  
COMMISSION  
DEC 10 1991  
12-10-91  
DIVISION

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1300' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

I hereby acknowledge and observe this plugging.

DATE 12-11-91  
INV. NO. 34137

Signed Stephen J. Pfeifer  
(TECHNICIAN)