

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File **ONE** Copy)

API # 15 09320650-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Wallace Oil & Gas, Inc. KCC LICENSE # 5855 *6/97*
(owner/company name) (operator's)

ADDRESS 3030 N.W. Expressway CITY Oklahoma City

STATE Oklahoma ZIP CODE 73112 CONTACT PHONE # (405) 948-1100

LEASE Van Doren WELL# 1 SEC. 22 T. 21 S R. 35 W (East/West)

SPOT LOCATION/0000 COUNTY Kearny

FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 614 CEMENTED WITH 405 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 2803 CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2725-32 2786-96 CIBP 2700 w/2 sacks 2660-64 2670-73

ELEVATION GL T.D. 2804 PBDT 2700 ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING CIBP+ 2 sacks cement at 2610 feet, cut casing at free point, run tubing to casing stub, circulate hole with 9.5# mud, pump 50 sacks cement, pull tubing to 714 feet, pump 75 sacks cement to 466 feet, wait 4 hours, tag cement, pull tubing to 40 feet, pump 15 sacks cement to surface, cut off wellhead weld on steel ID plate
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? _____

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. JAN 101 *1977* 1-17-97 AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Dennis Lee Holman PHONE# 806 665 2550

ADDRESS P.O. Box 2742 City/State PAMPA TX

PLUGGING CONTRACTOR H&K Plugging & Salvage KCC LICENSE # 31705 *6/97*

ADDRESS P. O. Box 2742 Pampa, TX. 79066-2742 PHONE # (806) 665-2550
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: _____ AUTHORIZED OPERATOR/AGENT: _____

(signature)



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 21, 1997

Wallace Oil & Gas Inc
3030 NW Expressway
Oklahoma City OK 73112

Van Doren #1
API 15-093-20,650-0000
N/A
Sec. 22-21S-35W
Kearny County

Dear Dennis Lee Holman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760