

RECEIVED

JAN 04 2002

KCC WICHITA

1-4-02

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-093-21380-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Fremont Exploration, Inc. KCC LICENSE # 31790
(owner/company name) (operator's)
ADDRESS 12412 St. Andrews Drive CITY Oklahoma City

STATE Oklahoma ZIP CODE 73120 CONTACT PHONE # (405) 936-0012

LEASE Hampton Estate WELL# 1-9 SEC. 9 T. 21S R. 35 (East/West)

SE -NW - NE - SPOT LOCATION/0000 COUNTY Kearney

4290 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

1650 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1930' CEMENTED WITH 775 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4842' CEMENTED WITH 225 SACKS *

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4492'-4581', 4577'-4581', & 4618'-4620'

ELEVATION 3165 GL T.D. 5000' PBD 4960' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Spot 25 sacks cement plug through tubing at 4450', spot 40 sk plug at 1960', spot 50 sk plug at 1030', spot 25 sk plug at 550'. Pump on 4 1/2 x 8 5/8" annulus to insure cement fill-up behind 4 1/2".

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? yes

If not explain why? This well acquired from Chesapeake Operating, Inc. successor to Hugoton Energy. Did not receive logs in transaction.
PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Robert Rowley PHONE# (620) 271-4719

ADDRESS P.O. Box 401 City/State Holcomb, KS 67851

PLUGGING CONTRACTOR Sargent & Horton Plugging, Inc. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS Liberal, KS PHONE # (620) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-116) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 01/02/02 AUTHORIZED OPERATOR/AGENT: Jean Conroy

* port collar set at 2803', cemented with 550 sx (TOC calculated to surface with excess)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Fremont Exploration, Inc.
12412 St. Andrews Drive
Oklahoma City, OK 73120

January 15, 2002

Re: HAMPTON ESTATE #1-9
API 15-093-21380-00-00
SEWNNE 9-21S-35W, 4290 FSL 1650 FEL
KEARNY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888