


This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR AMERICAN CONTINENTAL ENERGY API NO. 15-093-20,754-0000  
 ADDRESS 1845 Sherman St. Suite 665 COUNTY Kearny  
Denver, Colorado 80203 FIELD Panoma  
 \*\*CONTACT PERSON Karl G. Sieg LEASE Ella  
 PHONE 303-863-1227 PROD. FORMATION Council Grove  
 PURCHASER Northern Natural Gas WELL NO. #1  
 ADDRESS 2223 Dodge St. WELL LOCATION C-NW  
Omaha, Nebraska 68102 1320'Ft. from FNL Line and  
1300'Ft. from FWL Line of  
 the NW SEC. 29 TWP. 21 RGE. 37W  
 DRILLING CONTRACTOR Aldrill Exploration Corp.  
 ADDRESS 729 E. Central  
Wichita, Kansas 67211  
 PLUGGING CONTRACTOR N/A  
 ADDRESS N/A  
 TOTAL DEPTH 3052' PBDT 3052'  
 SPUD DATE 1/8/82 DATE COMPLETED 4/24/82  
 ELEV: GR 3327' DF KB 3332'



WELL PLAT  
 (Quarter) or (Full) Section - Please indicate.

KCC   
 KGS   
 MISC.

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(AIR)~~ TOOLS  
 Report of all strings set - surface, intermediate, production, etc. (New) / (Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	#20	322'	Class H	200	3% CaCl
Production	7 7/8"	5 1/2"	#14	3050'	Lite 50/50 Poz-Mix	400 200	18% NaCl

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			

TUBING RECORD			PERFORATION RECORD		
Size	Setting depth	Pecker set at	Shots per ft.	Size & type	Depth interval
2 3/8"	3013'	N/A	2 JSPF	3/8" JET	2924'-2944' (20')
			2 JSPF	3/8" JET	2975'-2996' (21')

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
HOWCO fraced well as follows: 1500 gals HCL, 100,000 gal slick water and 150,000 lbs of river sand at 150 BPM (total volume 2991 Bbl's).	2924'-2944'
	2975'-2996'

TEST DATE: Not Available PRODUCTION

Date of first production N/A Producing method (flowing, pumping, gas lift, etc.) Pumping A.P.I. Gravity N/A

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	<u>N/A</u> bbls.	<u>N/A</u> bbls.	<u>N/A</u> %	<u>N/A</u> bbls. CFPB

Disposition of gas (vented, used on lease or sold) N/A Producing interval(s) 2924'-2944', 2975'-2996'

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

4-29-82 APR 29 1982

CONSERVATION DIVISION  
 Wichita, Kansas

Name of lowest fresh water producing stratum Carlile Shale Depth 200'  
 Estimated height of cement behind pipe Circulated

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Stone Corral		2243'	GR/Neutron	(+1089)
Krider	2666'		" "	(+666)
Winfield	2708'		" "	(+624)
Lower Fort Riley	2801'		" "	(+531)
Council Grove	2887'		" "	(+445)
Five Finger	2923'		" "	(+409)
B-1	2975'		" "	(+357)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

**A F F I D A V I T**

STATE OF Colorado, COUNTY OF Denver SS,

Karl G. Sieg OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS Executive Vice President FOR AMERICAN CONTINENTAL ENERGY, INC. OPERATOR OF THE ELLA LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. #1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 24th DAY OF April 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) *Karl G. Sieg*

SUBSCRIBED AND SWORN TO BEFORE ME THIS 26th DAY OF April 1982

*Waltraud Mateev*  
 NOTARY PUBLIC  
 (WALTRAUD MATEEV)

MY COMMISSION EXPIRES: September 21, 1983