

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 68-23

LOCATION SW-SW-71W

SEC. 31 TWP. 21 RGE. 15-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Nansen

Operator Houder Drilling Co Address McBride Bldg - Gr. Bend - Kans.

Field _____ County Pawnee

Total Depth 3954 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 965 ft. - Circulated with cement.
5/8 casing at 3954 ft. - Cemented with 195 sacks cement.
Plugged back to 3480 ft with Low Wells Plug & shot.
Dumped 5 sacks of cement at 3480 ft. - Shot off & pulled
the 5/8 casing - need to 240 ft. - set rock bridge &
15 sacks of cement at 240 ft. - need to 30 ft. - Plug
& 10 sacks of cement at the surface.
Anneal Casing Pulling Co. - Plugging Contractor

4-5-51

RECEIVED
STATE CORPORATION COMMISSION

APR - 5 1951

CONSERVATION DIVISION
Wichita, Kansas

C. W. Stough
District Conservation Agent

Date 4-3-51

PLUGGING
FILE SEC. 31 TWP. 21 RGE. 15W
BOOK PAGE 68 OF 83