

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1972
CONSERVATION DIVISION
Wichita, Kansas

2-17-72

Operator's Full Name Ralph Lynch
Complete Address R. R. # 4 Great Bend, Kansas 67530
Lease Name Cade-Wittig Well No. 2
Location SE NE NE Sec. 30 Twp. 21 Rge. (E) (W) 15
County Pawnee Total Depth 3930'
Abandoned Oil Well XX Gas Well XX Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Ralph Lynch Csg. Pulling
Address Great Bend, Kansas 67530 License No. 457
Operation Completed: Hour 11 A Day 10 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 3930' 8 5/8 csg set at 935' cwc 16" csg set at 42' cwc.
5 1/2 csg set at 3930' cw 150 sk cmt.
Set 5 1/2 wood plug at 3500' -poured 15' sd -dumped 5 sk cmt W/dump bailer. (3450-3500)
Cutoff and recovered 2207' of 5 1/2 csg.
Mud to 507' -Filled with rock & sand (400-507)
Dumped 5 1/2 yds readymix cmt (0-400)

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2-17-72
INV. NO. 5189-WL

Signed: Geo. Massing
Well Plugging Supervisor