

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSIONJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUL 1 1974

CONSERVATION DIVISION
Wichita, Kansas

7-1-74

Operator's Full Name Braden-Deem, Inc.

Complete Address 200 East First Wichita, Kansas 67202

Lease Name Blasi Well No. 2

Location NW SE SE Sec. 2 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3911'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Casing Pulling

Address Box 373 Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour 4 P Day 27 Month 6 Year 1974

The above well was plugged as follows:

Total Depth 3911' 8 5/8 csg set at 1023' cwc 450 sk.5 1/2" csg set at 3911' cw 250 sk cmt.5 1/2 csg FBTD 3881' & perf. (3844)Filled 5 1/2 csg W/sd (3881-3830) dumped 4 sk cmt W/dump bailor. (3830-3800)Cutoff and recovered 2050' of 5 1/2 csg.Filled 8 5/8 csg with mud to 400' -set rock & sand brigde (400-380)Filled with readymix cmt from 380' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leot. Massey
Well Plugging Supervisor

INVOICED

DATE 7/2/74
IN.V. No. 9433-W