

15.145.00757.0000



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Braden-Deem, Inc.

Complete Address 200 East First, Wichita, Kansas 67202

Lease Name Blasi Well No. 1

Location NE SE SE Sec. 2 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3785'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Nicholas Pipe Pulling

Address Box 373, Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour 11:30 A Day 25 Month 6 Year 1974

The above well was plugged as follows:

Total Depth 3785' 8 5/8 csg set at 988' cwc 450 sk.

5 1/2 csg set at 3782' cw 100 sk cmt.

Filled 5 1/2 csg with sand (3785-3750) dumped 4 sk cmt W/dump bailer. (3720-3750)

Cutoff and recovered 3115' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 400' -set rock & sand bridge (400-380)

Filled with readymix cement from 380' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Len F. Massey  
Well Plugging Supervisor

INVOICED

DATE 7/1/74

INV. NO. 9409-W