



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Braden-Deem, Inc.

Complete Address 200 East First, Wichita, Kansas 67202

Lease Name Kindsvater Well No. 1

Location SE SE NE Sec. 2 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3805'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Nickolas Casing Pulling

Address Box 373 Gensee, Kansas License No. 711

Operation Completed: Hour 10:30 A Day 31 Month 5 Year 1974

The above well was plugged as follows:

RTD 3805' 8 5/8 csg set at 1015' cwc 475 sk.

5 1/2 csg set at 3795' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (3805-3780) dumped 4 sk cmt W/dump bailer. (3780-3750)

Cut ~~off~~ and recovered 2781' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 450' -set sand & rock bridge (450-420)

Filled with readymix cement fro 420' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massy  
Well Plugging Supervisor

INVOICED

DATE 6/4/74

INV NO. 9233-W