

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1965

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Alpine Oil & Royalty

Complete Address: ~~Kindsvatter~~ 800 Bitting Bldg Wichita, Kans

Lease Name Kindsvatter Well No. 2

Location NW SE NE Sec. 2 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 5790

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Operation Completed: Hour 1PM Day 14 Month 10 Year 65

The Above well was plugged as follows:

8 5/8" 1022' circulated with 4/5 sax cement - 5 1/2" 3780' with 100 sax cement

Sand to 5770', set 4 sax cement with dump bailer - pulled 5100' 5 1/2"

to 700', circulated hole with heavy gel mud through 5 1/2" - pulled 5 1/2"

to 400', displaced 20 sax cement through 5 1/2" - heavy mud to 200',

displaced 20 sax cement through 5 1/2", heavy mud to 55', cement 55' to bottom

cellar.

Mudding and cementing by Glenn & Smith pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Glenn Smith
Well Plugging Supervisor

DATE 10/20/65
INV. NO. 2005-W