

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-145-20750-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name MID AMERICA PRODUCERS, INC.

Complete Address BOX 18163 OKLAHOMA CITY, OKLAHOMA 73154

Lease Name BRADLEY Well No. #1

Location SW - SE Sec. 5 Twp. 21 Rge. 16 (East) (West)

County PAWNEE Total Depth 2567 ^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor HELSO CASING PLUGGING. (BUCK LINRUH)

Address BOX 176 CHASE, MAN'S. License No. _____

Operation Completed: Hour: 3:30 PM Day: 30th Month: APRIL Year: 19 81

The above well was plugged as follows:

8 5/8" 1028^{FE} SP. CEMENT - 4 1/2" SET @ 2547^{FE} 1/50ST CMT.
PLUG. BACK. 2080^{FE} - PERFS 2024^{FE} TO 32^{FE} - HELSO SANDED
BOTTOM OF HOLE TO 2000^{FE} 1/4ST CMT. - RECOVERED 1830^{FE} OF PIPE.
ORDERED 140ST 50ST PORNIX 6% GEL. - 3% CA-CL -> 20ST GEL.
5ST HULL'S - + 8 5/8" PLUG -> PUMPED IN 8 5/8" WITH PUMP TRUCK.
PUT IN - 5ST HULL'S -> 10ST GEL -> RELEASED PLUG AND
140ST CMT. -> MAX PRESSURE 1100^{PSI} -> SHUT IN @ 800^{PSI}
CEMENTED BY ALLIED CMT.

RECEIVED
STATE CORPORATION COMMISSION
MAY - 4 1981
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Maurin Schmidt
Conservation Division Agent

INVOICED
DATE 5-28-81
INV. NO. 5525-W