



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Roy Cook of Imperial Oil Company, has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: 780 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Foster Well No. 1

Location: SW-SW-NE Sec. 12 Twp. 21 Rge. (E)(W) 16

County: Pawnee Total Depth 3791' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

965'--8 5/8" Surface casing, cement circulated with 450 Sx.
Surface casing set 18' in Anhydrite.

Circulate hole with heavy mud. Pull DP to 360' and displace 25 Sx.
cement thru DP. Pull DP to 185' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 3 1969
 CONSERVATION DIVISION
 Wichita, Kansas

Very truly yours,

Conservation Division Agent