

ATE OF KANSAS
ATE CORPORATION COMMISSION
0 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-145-21,383-0000

LEASE NAME Phinney

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 1 TWP. 21S RGE. 16W (E) or (W)

COUNTY Pawnee

Date Well Completed

Plugging Commenced 5-7-98

Plugging Completed 5-12-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John Shada

ADDRESS 4126 N. Sweet Bay Circle, Wichita, Ks. 67226

PHONE# (316) 636-2525 OPERATORS LICENSE NO. 3833

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3895'

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1003'	None
				5-1/2"	3894'	2428'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 3700' and 5 sacks cement. Shot pipe @ 3000', 2800', 2600' and 2418'. Pulled up to 1030', pumped 10 sks. gel and 50 sks. cement, pulled to 500', pumped 40 sks. cement, pulled to 40' and circulated 10 sks. cement to surface. 60/40 pos. 6 1/2 gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 98

[Signature]
Notary Public

My Commission Expires:



Form CP
Revised 05-