


WELL PLUGGING RECORD

Give All Information Completely
Make Required A... with
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Pawnee County. Sec. 1 Twp. 21 Rge. 16 (W) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW
Lease Owner BEN F. BRACK OIL COMPANY, INC.
Lease Name SPREIER Well No. 1
Office Address 309-10 Brown Building
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 10/20/ 19 48
Application for plugging filed 12/29/ 19 50
Application for plugging approved 12/29/ 19 50
Plugging commenced 12/29/ 19 50
Plugging completed 12/29/ 19 50
Reason for abandonment of well or producing formation
nothing there
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Oral

Name of Conservation Agent who supervised plugging of this well Mr. D. C. Stough
Producing formation Arbuckle Depth to top 3780 Bottom Total Depth of Well 3785 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|--------------------|-----------|-------|----|--------|--------|------------|
| Sand, Gravel, Clay | no show | 275' | | 8 5/8" | 584' | |
| Arbuckle Lime | fair odor | 3785' | | 4 3/4" | 3787' | 3389.76' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3743 feet to 30 feet for each plug set.
Filled with mud -
Set top plug at 30' and cemented with 250 sacks cement.
Cemented bottom with 100 sacks cement
Filled and leveled hole.

1-18-51

JAN 18 1951
NOTARY PUBLIC
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Ben F. Brack Oil Company, Inc.
Address 309-10 Brown Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
BEN F. BRACK OIL COMPANY, INC.
309 Brown Building Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of January, 1951
V. E. Evans
Notary Public.

My commission expires November 1, 1954

PLUGGING
FILE SEC. 1 T. 21 R. 16
BOOK PAGE 52 LINE 41

BEN F. BRACK OIL COMPANY, INC.
 310 Brown Building
 Wichita, Kansas

Spreier #1 SE SE NW, Section 1, T. 21 S., R. 16 W., Pawnee County, Kansas

WELL LOG

| | |
|-------------------------------|---------------|
| TOTAL DEPTH | 3788' |
| Comm: 10-20-48 | Comp: 11-5-48 |
| Cellar | 5' |
| Sand, gravel and blue clay | 275 |
| Shale | 405 |
| Sand | 520 |
| Red Bed | 580 |
| Shale, shells and red bed. | 960 |
| Red Bed | 980 |
| Anhydrite | 1020 |
| Red Salt and Shale | 1255 |
| Shale, Shells and Salt | 1515 |
| Shale and salt | 1760 |
| Sandy Lime | 1945 |
| Lime | 2090 |
| Lime | 2175 |
| Lime | 2280 |
| Lime | 2355 |
| Lime and shale | 2460 |
| Lime and Shale | 2690 |
| Lime and Shale | 2805 |
| Lime and Shale | 2950 |
| Lime and Shale | 3050 |
| Lime and Shale | 3145 |
| Lime and Shale | 3175 |
| Lime and Shale | 3230 |
| Lime and Shale | 3280 |
| Lime and Shale | 3380 |
| Lime and Shale | 3370 |
| Lime and Shale | 3440 |
| Lime and Shale | 3490 |
| Lime | 3550 |
| Lime | 3590 |
| Lime and Shale (Conglomerate) | 3655 |
| Conglomerate | 3715 |
| Conglomerate | 3745 |
| Conglomerate | 3771 |
| Arbuckle | 3780 |
| Arbuckle Lime | 3785 |
| TOTAL DEPTH | 3788 |
| (corrected to 3785') | |

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 18 1951

CONSERVATION DIVISION
 Wichita, Kansas

To the best of my knowledge the above is a true and correct record of the formations and depths where found.

Dated: November 11, 1948

Witness: Pauline Hendrickson

BEN F. BRACK OIL COMPANY, INC.

By: Paul Brack

PLUGGING
 FILE SEC LT 21 R 16c
 WORK PAGE 52